

TECHNICAL SPECIFICATION FOR CIVIL WORKS

1. STRUCTURE :

- STRUCTURE WILL BE DESIGNED OF FRAMED STRUCTURE
- FOUNDATION TRENCHES SHALL BE DUG OUT TO THE EXACT LENGTH, BREADTH, AND DEPTH FROM NORMAL GROUND LEVEL AS PER ISSUED DRAWING
- EXCAVATION OF FOOTING UP TO HARD STRATUM FROM THE GROUND LEVEL WILL BE IN OUR SCOPE.
- PCC SHALL BE 100MM THICK CONCRETE SHALL BE MIXED PROPERLY, RAMMED AND LEVELLED WELL
- SUPPLYING AND ERECTING CENTERING MATERIALS WITH NECESSARY SUPPORTS FOR PLAIN SURFACES SUCH AS REINFORCED CEMENT CONCRETE FOOTINGS, COLUMNS, PLINTH BEAMS, LINTEL BEAM ROOF BEAM & ROOF SLAB ETC.,
- ALL THE RCC STRUCTURES LIKE FOOTINGS, COLUMNS, PLINTH BEAMS, LINTEL BEAM ROOF BEAM & ROOF SLAB ARE PROVIDED WITH M20 GRADE CONCRETE
- CUT LINTEL WILL BE PROVIDED ON ALL DOOR & WINDOW WITH 9 INCH BEARING ON BOTH SIDE
- SLAB CONCRETE SHALL BE 125MM THICK & CONCRETE MAY BE SITE MIX OR RMC ACCORDING TO CONTRACTOR CONVINCE
- EARTH FILLING AND SOIL CONSOLIDATION SHALL BE CARRIED UP TO FINISHED FLOOR LEVELS
- FINISHED FLOOR LEVEL SHALL BE OF 2.25 FEET FROM THE ROAD LEVEL AND PARKING AREA SHALL BE OF 1.5 FEET FROM THE ROAD LEVEL
- BASIC PEST CONTROLL SHALL BE CARRIED BEFORE THE FLOORING P.C.C
- DOUBLE WASH M SHALL BE USED FOR CONCRETE WORKS
- FLOOR SHALL BE OF 11 FEET FROM ROUGH FLOOR LEVEL.

2. **MASONRY WORKS :**

- SUFFICIENT QUANTITY OF RED BRICKS & FLY ASH BRICKS SHALL BE SUPPLIED BY CONTRACTOR
- RED BRICKS & FLY ASH WALL OF 9 INCH FOR EXTERIOR & 4.5 INCH FOR INTERIOR WALL
- CEMENT MORTAR FOR BRICK WORK SHALL BE 1:6 CEMENT MORTAR
- M – SAND SHALL BE USED FOR BRICK WORK
- EACH AND EVERY COURSE SHALL BE DONE TO PLUMB
- STAIRCASE WAIST SLAB WITH CONCRETE, THREAD AND RISER WILL BE WITH BRICKS (MS STAIRCASE IS NOT PART OF PACKAGE).
- BALCONY , TERRACE & UTILITY AREA WILL BE PROVIDED WITH 3' FEET HEIGHT BRICKWORK PARAPET WALL
- CEMENT - PPC OF GRADE - 43 FOR BOTH BRICKWORK & PLASTERING (JSW OR EQUIVALENT)
- FINE QUALITY OF P – SAND SHALL BE USED FOR INTERNAL AND EXTERNAL PLASTERING
- INTERNAL PLASTERING (1:5 CEMENT MORTAR), EXTERNAL PLASTERING (1:5 CEMENT MORTAR), AND CEILING PLASTERING (1:4 CEMENT MORTAR) SHALL BE DONE WITH MINIMUM OF 12MM THICKNESS.
- STEEL SHUTTERS SHALL BE REMOVED AND HACKED WELL FOR PLASTERING
- INTERNAL & EXTERNAL PLASTERING WALLS SHALL BE FINISHED SMOOTHLY BY STEEL FLOAT OR SPONGE
- WATER CUTTING BORDERS FOR CHEJJAS WILL BE PROVIDED
- POINTING ALL THE CORNERS AND EDGES SHALL BE DONE WITH CEMENT MORTAR RATIO OF 1:4

3. DOORS & WINDOWS:

MAIN DOOR :

- MAIN DOOR FRAME ARE PROVIDED WITH WELL-SEASONED COUNTRY TEAK OF WOOD SIZE 5"X4" OR 6"X3"
- MAIN DOOR IS PROVIDED WITH TEAK DOOR OF 40MM THICKNESS
- MAIN DOOR OPENING SIZE SHALL BE 4'3" FEET * 7'6" FEET
- MAIN DOOR LOCKS WILL BE PROVIDED WITH CYLINDRICAL LOCK (MAKE EUROPA OR DORSET) AT THE RATE OF RS 3,000/-
- MAIN DOORS WILL BE PROVIDED WITH 4NOS OF BALL BEARING HINGES, 2NOS OF TOWER BOLTS (MAKE: BRASS)

INTERNAL DOORS :

- ALL INTERNAL DOOR FRAMES ARE PROVIDED WITH WELL-SEASONED SAL WOOD SIZE 5"x 3" THICK
- ALL INTERNAL DOORS ARE PROVIDED WITH ANY READY-MADE FLUSH DOORS AT THE COST OF RS.3000/NOS
- INTERNAL DOOR OPENING SIZE SHALL BE 3'3" FEET * 7'6" FEET
- ALL INTERNAL DOORS ARE PROVIDED WITH 3NOS OF HINGES AND 2NOS OF TOWER BOLTS & DOOR STOPPER (MAKE SS)
- INTERNAL DOOR LOCKS WILL BE PROVIDED AT THE RATE OF RS 1200/-

BATH ROOM DOORS :

- ALL BATHROOM DOORS ARE PROVIDED WITH PVC
- BATHROOM DOORS WILL BE SINGLE PANEL DOOR
- BATHROOM OPENING SIZE SHALL BE 2'6" FEET * 7'0" FEET

WINDOWS :

- ALL WINDOWS ARE PROVIDED WITH UPVC (OPEN OR SLIDING WINDOW)
- ALL THE WINDOW GLASSES ARE PROVIDED WITH 5MM PLAIN GLASS
- ALL THE DOORS AND WINDOWS OPENINGS ARE PROVIDED WITH APPROVED SIZES. MS GRILLS ARE PROVIDED FOR WINDOWS WITH 12MM SQ. RODS.
- THE TOTAL AREA OF OPENING FOR WINDOWS AND VENTILATORS INCLUDING FRAMES IN THE PACKAGE IS 15% OF THE BUILT UP AREA.

- WINDOW CHAJJA IS PROVIDED AS PART OF THE PACKAGE – UPTO 1.5 FEET OUTWARD PROJECTION AND 9” BEARING ON EACH SIDE OF WINDOW.

4. KITCHEN / PANTRY:

- CONCRETE COUNTER TOPS ARE PROVIDED WITH 3” THICK AS PER DRAWING.
- COUNTER TOPS ARE FINISHED WITH GRANITE AT THE COST OF RS 120/SQFT
- KITCHEN SINKS ARE PROVIDED WITH SS MAKE AT THE SIZE 2’ LENGTH, 1.5’ WIDTH AND 1’ DEPTH OF WORTH RS.2500
- KITCHEN WALL TILES SHALL BE PROVIDED UPTO 7’ HEIGHT ABOVE THE KITCHEN COUNTER SLAB
- PROVISION FOR WATER PURIFIER WILL BE GIVEN NEAR TO MAIN SINK.
- EXHAUST FAN PROVISIONS SHALL BE PROVIDED WITH 9” CORE CUTTING HOLES IF DESIRED.
- MAIN SINK FAUCETS ARE PROVIDED AT THE COST OF RS 2500/NOS

5. BATHROOM/TOILETS:

- BASIC WATER PROOFING OF DR.FIXIT OR FOSROC 2 COATS WILL BE PROVIDED
- SUNKEN SLABS ARE FILLED WITH BROKEN BRICKBAT AND FINISHED WITH CEMENT MORTAR
- ALL THE TOILETS ARE PROVIDED WITH 1 NO OF FLOOR MOUNTED WESTERN CLOSET, 2 IN 1 WALL MIXERS, HEAD SHOWER, HEALTH FAUCET AND WASH BASIN
- HOT WATER PROVISIONS ARE PROVIDED ONLY FOR WALL MIXERS
- SANITARY WARE & CP FITTINGS (BRAND: PARRYWARE BASIC MODEL)

- WASHING MACHINE PROVISION WILL BE GIVEN AS PER CLIENT CHOICE
- GEYSER PROVISION OF 16AMPS WILL BE GIVEN TO EACH BATHROOM.
- TOILETS VENTILATORS OPENS ARE PROVIDED UP TO 2x3 FEET SIZES
- TOILET OPENS ARE PROVIDED WITH UPVC VENTILATORS WITH FIXED GLASS AND EXHAUST FAN HOLES.

6. FLOORINGS :

- SURFACE SHALL BE WELL CLEANED AND DEAD MORTAR TO BE CHIPPED BEFORE FLOORING.
- TERRACE FLOORING SHALL BE CARRIED OUT BY COMPLETE WATER PROOFING FOLLOWED BY CHIPS CONCRETE FLOORING.
- WATER PROOF CHEMICAL COMPONENTS SHALL BE ADDED TO CEMENT MORTAR FOR SCREED CONCRETE.
- FLOORING TILES SHALL BE LAYED WITH CEMENT MORTAR OF RATIO 1:5
- INTERNAL FLOORING TILES SHALL PROVIDE WITH PAPER JOINT.
- ALL THE TILES JOINTS ARE FINISHED WITH POWDER GROUTS.
- 4" INCHES SKIRTINGS TILES SHALL BE PROVIDED FOR LIVING, BED ROOMS AND KITCHEN.
- ALL THE FLOORING TILES COST PROVIDED BY CONTRACTOR IS RS.50/SFT
- ALL THE WALL TILES LIKE KITCHEN, TOILET WALLS COST PROVIDED BY CONTRACTOR IS RS.40/SFT
- PORTICO FLOORING TILES COSTS PROVIDED BY CONTRACTOR IS RS.50/SFT
- STEPS THREADS & RISERS ARE PROVIDED WITH LEATHER FINISH GRANITE AT THE COST OF RS 120/SFT
- ALL THE BATHROOMS ARE PROVIDED WITH VETRIFIED WALL TILES UP TO 7' LEVEL HEIGHT AT THE COST OF RS 40/SFT

- ALL THE BATHROOMS FLOORING TILES ARE PROVIDED WITH 1'3"X1'3" VETRIFIED FLOOR TILE AT THE COST OF RS45/SFT
- BATHROOM FLOORS TILES ARE PROVIDED WITH 3MM SPACER JOINT AND SPACERS ARE FILLED WITH EPOXY GROUT
- FLOORING/DADO/SKIRTING MUST LEVEL TO PLUMB.

7. ELECTRICAL:

- ALL THE INTERNAL ELECTRICAL WIRING PIPES AND SWITCH BOARDS ARE FIXED IN CONCELED MANNER
- ALL THE SWITCH BOXES ARE PROVIDE WITH MODULAR METAL BOXES AT LEGRAND / GM BRANDS
- ALL POSITION OF SWITCH BOXES SHALL BE FIRST MARKED ON THE BUILDING ITSELF AND APPROVED BY OWNER
- ALL THE WIRING SHALL BE DONE ON THE DISTRIBUTION SYSTEM WITH MAIN AND BRANCH DISTRIBUTION AT COVENIENT
- EACH SUB-CIRCUIT SHALL BE PROTECTED BY FUSE / MCB
- WHEN CONDUITS PASS THROUGH WALL AND FLOOR ,THE CONDUITS SHALL BE WIRED THROUG 1.5MM PVC SLEEV PIPES OF APPROVED ISI MAKES
- ALL THE CEILING POINT CONDUITS ARE PASS THROUGH 2MM PVC SLEEV PIPE OF APPROVED ANY ISI MAKE
- WIRES (KUNDAN)
- SWITCHES & SOCKETS HIFI
- DISTRIBUTION BOARD SHALL BE PROVIDED (LEGRAND OR EQUIVALENT).
- PROVISIONS FOR UPS SHALL BE PROVIDED IN ALL SWITCH BOXES
- COST OF MAIN EB SERVICE WORK AND COST OF CABLE AND PANEL WORK ARE NOT UNDER OUR SCOPE
- ALL ELECTRICAL POINTS IN LIVING/DINING/FAMILY HALL SHALL BE PROVIDE AS PER THE ARCHITECTURAL DRAWING

8. PLUMBING:

- PLUMBING SHALL BE FULLY OPERATIONAL SYSTEM OF COLD WATER. PROVIDE AND INSTALL ALL PIPING, VENTS, DRAINS, SEWAGE REMOVAL AND WATER SUPPLY SYSTEM
- WATER SUPPLY INLET LINE SHALL BE TAKEN FROM GROUND WATER BORE TO OVER HEAD TANK. SUPPLY LINES CAN BE CARRIED WITH 1.25" INCHES OF UPVC PIPES
- OUTLET WATER LINE SHALL BE TAKEN IN 1.25" INCHES OF UPVC PIPES
- INTERNAL CONCEALED WATER PIPES ARE PROVIDED WITH 0.75 INCH CPVC PIPE.
- WASTE WATER FROM TOILETS AND KITCHEN SHALL BE TAKEN 2.5" INCHES PVC PIPES
- SEWAGE LINE FROM TOILET TO SEPTIC TANK SHALL TAKEN 4" / 4 GAUGE PVC PIPES
- WASTE WATER CHAMBER, SEWAGE CHAMBER SHALL BE PROVIDED BASED ON SITE CONVENIENT
- RAIN WATER LINES FROM TERRACE SHALL TAKEN IN 4" / 4 GAUGE PVC PIPES
- SOLAR WATER PROVISIONS IN KITCHEN AND BATHROOM SHALL BE PROVIDED
- CORPORATION WATER LINE TO SUMP SHALL BE PROVIDED
- INTAKE OF CORPORATION WATER FROM SUMP TO OVER HEAD TANK SHALL BE DONE.
- ALL THE MANHOLES ARE PROVIDED WITH 2' x 2' FRP LIDS
- SEWAGE LINE CHAMBERS ARE CLOSED WITH 30MM KADAPPA STONE

9. PAINTINGS:

- PREPARATION OF ALL TYPE OF SURFACES TO BE PAINTED BY REMOVING ALL LOOSE MATERIALS,DUST,STAIN ETC...
- ALL THE INTERNAL WALLS AND CEILINGS ARE PROVIDED WITH 2 COATS OF INTERANAL WALL PUTTY (MAKE:ASIAN)
- SURFACE SHOULD BE BUFFING THROUGHLY BY USING EMERY PAPERS,BUFFING WHEELS AFTER THE COMPLETION OF PUTTY
- ALL THE INTERNAL SURFACE ARE APPLY WITH ONE COAT INTERIOR PRIMER(MAKE ASIAN)
- TWO COATS OF ASIAN PAINTS(TRACTOR EMULSION) COLOURS SHALL BE PROVIDED
- ONE COAT OF BIRLA WHITE SHALL BE APPLIED FOR EXTERNAL WALL
- ONE COAT OF EXTERAL PRIMER SHALL BE PROVIDED IN EXTERIOR WALLS(MAKE ASIAN)
- TWO COATS OF (ASIAN PAINTS ACE) COLOURS WILL BE APPLY FOR EXTERIOR SURFACES
- ALL THE MS WINDOW GRILLS ARE PROVIDED WITH ONE COAT OF ANTI CORROSION PRIMER AND TWO COATS OF ENAMAL PAINT
- ALL THE INNER DOORS FRAMES ARE PROVIDE WITH 2 COATS OF ENAMEL PAINT.
- MAIN DOOR FRAMES ARE PROVIDED WITH 2 COATS OF MALAMINE POLISH.

10. MISCELLANEOUS:

- **IF ROCK ENCOUNTERS AT THE TIME OF EXCAVATION, ROCK DRILLING WILL COST EXTRA**
- IF OVERHEAD TANK WILL BE PROVIDED IN RCC WHICH WILL BE CHARGED EXTRA ON MUTUAL UNDERSTANDING BASIS
- UNDERGROUND SUMP WITH BRICKWORK(FLYASH) & CONCRETE COVERSLAB – 6000LTR

- STAIRCASE RAILING SHALL BE DONE ON SS HANDRAIL.
- MAIN GATE (NOT INCLUDED IN PACKAGE) SHALL BE DONE ON MUTUALLY UNDERSTANDING BASIS.
- COMPOUND WALL (NOT INCLUDED IN PACKAGE) SHALL BE DONE ON MUTUALLY UNDERSTANDING BASIS.
- FRONT ELEVATION WITH BASIC CIVIL WORKS OF THE BUILDING SHALL INCLUDE IN OUR PACKAGE
- ADDITIONAL LIFTING OF STRUCTURE ABOVE 2'6" FT WILL CHARGE EXTRA ON PRO-RATA COST, WORKED OUT BY THE CONTRACTOR.
- UNDER GROUND SEPTIC TANK OF 4000 LTR WILL BE PROVIDED.
- 2 NOS OF 1000 LTR OVERHEAD PVC TANK WILL BE PROVIDED.
- FINAL BILL WILL BE TAKEN ON SITE WITH ACTUAL MEASUREMENTS

ANY ITEM WHICH IS NOT MENTIONED IN THE SPECIFICATION IS AN EXCLUSION

MATERIAL SPECIFICATIONS FOR CIVIL WORKS:

S.NO	DESCRIPTION	BRAND	RATE
1	CEMENT	JSW OR EQUIVALENT ULTRATECH FOR CONCRETE	400/BAG
2	STEEL	VIZAG OR AGNI	80/KG
3	M SAND	OPTIONAL	-----
4	P SAND	OPTIONAL	-----
5	BRICKS	CHAMBER RED BRICKS	10.50/NO
6	FILLING MATERIAL	SOIL/M SAND DUST	2000/UNIT
7	PLUMBING	ASTRAL	-----
8	ELECTRICAL	KUNDAN CABLES/ HIFI SWITCHES	MENTIOND IN SPEC
8	PAINTING	ASIAN PAINTS	-----
9	WINDOW GRILLS	MS 12 SQ.MM	75/KG
10	UPVC WINDWOS	EITI OR BAYDEE	450/SFT
11	TILES	-----	MENTIOND IN SPEC
12	SANITRY FITTINGS AND CP FITTINGS	PARRYWARE BASIC MODEL	-----

